AR77.21-P-1000T
 Remove/install panoramic sliding roof drive unit

 MODEL
 203.7, 211.0 with CODE (413) Panoramic sliding roof

 MODEL
 211.0

 with CODE (413) Panoramic sliding roof


 with CODE (413) Panoramic sliding roof

 with CODE (419) Solar module for panoramic roof

Shown on model 211.0

1 Bolts

M12Roof system drive unit (model203.7)M12/6Panoramic sliding roof driveunit (model 211.0)N70Overhead control panel controlunit



Modification notes

	18.7.06	Only loosen headliner, do not remove.	Steps 3.1, 3.2	
--	---------	---------------------------------------	----------------	--

XX	Remove/install		
⚠ Danger!	Risk of injury caused by fingers being pinched or crushed when removing, installing or aligning hoods, doors, trunk lids, tailgates or sliding roof.	Keep body parts and limbs well clear of moving parts.	AS00.00-Z-0011-01A
1	Close front glass roof		
2	Completely open sliding roof lining or roller sun blind	i According to vehicle model	
3.1	Loosen front headliner and insert spacer until roof system drive unit (M12) is accessible.	Model 203.7	AR68.30-P-4300PB
3.2	Loosen front headliner and insert spacer until panoramic sliding roof drive unit (M12/6) is accessible.	Model 211.0	AR68.30-P-4300TB
4	Remove bolts (1)	i Installation: Uniformly tighten bolts (1).	*BA77.20-P-1002-01A
5	Install in the reverse order		
6	Normalize roof system drive unit (M12) or panoramic sliding roof drive unit (M12/6)	i According to vehicle model	

Nm Electric sliding roof

Number	Designation			Model 203.7	Model 211
BA77.20-P-1002-01A	Bolt to sliding roof drive	Torx	Nm	4	4
		Hexagon socket	Nm	4	-