


GF07.61-P-5000-03AM	ME-SFI control unit - design		
---------------------	------------------------------	--	---



P07.08-2018-07

1, 2, 3 Engine plug
 4, 5 Vehicle plug (body)

The cable connections are performed by means of 5 plug sockets.

The ME control unit (N3/10) consists of aluminum and is designed as a shell concept unitary housing. It is designed for installation in a protective housing (e.g. relay and fuse box).

In addition, a pressure sensor for measuring the absolute pressure is integrated in the ME 2.8.1 control unit.