



Table of Contents

1	General Information
2	What's New
3	Models
4	Equipment
4.1	Standard Equipment
4.2	Exterior Paint Colors
4.3	Wheels
4.4	Interior Upholstery
4.6	Interior Trims
4.7	Packages
4.8	Options
4.9	Specifications
5	Options In Detail
6	Gallery

General Information

Important Note

The information presented in this guide is based on the most current information available and is intended for internal use only. Mercedes-Benz reserves the right to make changes at any time, without notice, to colors, materials, equipment, special specifications and models.

Pricing may not yet be finalized for some models or options.

Due to variances among monitors and printers the colors that appear on your screen and printouts may not be exact.

For illustrative purposes, some images may show vehicles with European Specification.

Revision History

Date	Description
02/29/2024	For MY24 942 - Load Compartment Package (\$485) will be required by Factory.
11/08/2023	GT55 Initial Publication
10/09/2023	GT63 Initial Publication

What's New

All-New Model

Models



GT55R4 (192.380)

- MSRP: TBD
- Transmission: AMG SPEEDSHIFT MCT 9G (9 speed)
- Acceleration 0-60 mph (sec): 3.8 (est)
- Engine Configuration: Handcrafted AMG 4.0L V8 biturbo
- Power (hp): 469 hp @ 5,500 - 6,500
- Torque (lb-ft): 516 lb-ft @ 2,500 - 5,000
- Launch Date: Spring/Summer 2024



GT63R4 (192.378)

- MSRP: TBD
- Transmission: AMG SPEEDSHIFT MCT 9G (9 speed)
- Acceleration 0-60 mph (sec): 3.1 (est)
- Engine Configuration: Handcrafted AMG 4.0L V8 biturbo
- Power (hp): 577 hp @ 5,500 - 6,500
- Torque (lb-ft): 590 lb-ft @ 5,500 - 6,500
- Launch Date: Spring/Summer 2024

Standard Equipment

GT55R4



Performance & Handling

- Handcrafted AMG 4.0L V8 Biturbo engine
- AMG Performance 4MATIC+
- Rear Axle Steering
- AMG DYNAMIC SELECT
- Rear Spoiler
- AMG Performance Exhaust
- AMG Yellow Brake Calipers
- AMG SPEEDSHIFT MCT 9-speed Transmission
- AMG ACTIVE RIDE CONTROL suspension
- 20" AMG Wheels
- Electronic Rear Limited-Slip Rear Differential
- AMG Performance Steering Wheel w/ Shift Paddles
- AMG Track Pace
- AMG Drive Unit Steering Wheel Buttons

Comfort & Convenience

- 12.3" Widescreen Instrument Cluster
- MBUX Infotainment and Navigation System
- Burmester® Surround Sound System
- SiriusXM® Radio All-Access w/ Trial Period
- Inductive Wireless Charging w/ NFC Pairing
- LED Headlamps and Taillamps
- Heated front seats
- KEYLESS-START
- Electronic Trunk Closer
- Mercedes me connect
- Garage door opener
- Load Compartment Package with 12V socket in trunk
- 11.9" Central Media Display
- "Hey Mercedes" Voice Control
- Bluetooth® connectivity
- Please note: the GT does not feature AM radio.
- Smartphone integration with Apple CarPlay™ & Android Auto
- Power front seats w/ 3-position memory and 4-way power driver's lumbar support
- Power Folding Mirrors
- KEYLESS-GO w/ HANDS-FREE ACCESS
- Power Tailgate
- AMG Illuminated Door Sills
- Heated Steering Wheel

Safety & Security

- Surround-View Camera
- ATTENTION ASSIST®
- Crosswind Assist
- Adaptive Highbeam Assist
- PRE-SAFE Sound
- Blind Spot Assist
- Active Brake Assist
- Car-to-X Communication
- LED Headlamps, Daytime Running Lights and Taillamps
- PRE-SAFE®
- Tire pressure monitoring system
- Active Parking Assist

Performance & Handling

- Handcrafted AMG 4.0L V8 Biturbo engine
- AMG Performance 4MATIC+
- Rear Axle Steering
- AMG DYNAMIC SELECT
- Rear Spoiler
- AMG Performance Exhaust
- AMG Yellow Brake Calipers
- AMG SPEEDSHIFT MCT 9-speed Transmission
- AMG ACTIVE RIDE CONTROL suspension
- 20" AMG Wheels
- Electronic Rear Limited-Slip Rear Differential
- AMG Performance Steering Wheel w/ Shift Paddles
- AMG Track Pace
- AMG Drive Unit Steering Wheel Buttons

Comfort & Convenience

- 12.3" Widescreen Instrument Cluster
- MBUX Infotainment and Navigation System
- Burmester® Surround Sound System
- SiriusXM® Radio All-Access w/ Trial Period
- Inductive Wireless Charging w/ NFC Pairing
- LED Headlamps and Taillamps
- Heated and ventilated front seats
- KEYLESS-START
- Electronic Trunk Closer
- Mercedes me connect
- Garage door opener
- Head-Up Display
- 11.9" Central Media Display
- "Hey Mercedes" Voice Control
- Bluetooth® connectivity
- Please note: the GT does not feature AM radio.
- Smartphone integration with Apple CarPlay™ & Android Auto
- Power front seats w/ 3-position memory and 4-way power driver's lumbar support
- Power Folding Mirrors
- KEYLESS-GO w/ HANDS-FREE ACCESS
- Power Tailgate
- AMG Illuminated Door Sills
- Heated Steering Wheel
- Load Compartment Package with 12V socket in trunk

Safety & Security

- Surround-View Camera
- ATTENTION ASSIST®
- Crosswind Assist
- Adaptive Highbeam Assist
- PRE-SAFE Sound
- Blind Spot Assist
- Active Brake Assist
- Car-to-X Communication
- LED Headlamps, Daytime Running Lights and Taillamps
- PRE-SAFE®
- Tire pressure monitoring system
- Active Parking Assist

Paint

Non-Metallic Paints



914 - Sun Yellow

Metallic Paints



197 - Obsidian Black



922 - Cirrus Silver



970 - Starling Blue



992 - Selenite Grey

MANUFAKTUR Paints



593 - Starling Blue Magno



659 - Moonlight White Magno



885 - Moonlight White Metallic



956 - Alpine Grey
Non-metallic




964 - Hyper Blue Magno




993 - Patagonia Red Metallic

<i>Code</i>	<i>Description</i>	<i>Availability</i>	<i>Price</i>
914	Sun Yellow	All Models	\$0
197	Obsidian Black	All Models	\$0
922	Cirrus Silver	All Models	\$0
970	Starling Blue	All Models	\$0
992	Selenite Grey	All Models	\$0
593	Starling Blue Magno	All Models	
659	Moonlight White Magno	All Models	
885	Moonlight White Metallic	All Models	
956	Alpine Grey Non-metallic	All Models	
964	Hyper Blue Magno	All Models	
993	Patagonia Red Metallic	All Models	


Wheels



DELAYED



DELAYED



RTM - 20" AMG Aero Twin 10-Spoke

20"

B51; R01

20" AMG Aero Twin 10-Spoke

295/30 R20 on 10.5J x 20 ET42 (front);
305/30 R20 on 11J x 20 ET33 (rear)

RVN - 20" AMG Multispoke

20"

B51; R01

20" AMG Multispoke

295/35 R20 on 10.5J x 20 ET42 (Front);
305/35 R20 on 11J x 20 ET33 (Rear)

**RWI - 21" AMG Forged Split 5-Spoke
Wheels, Silver**

21"

B51; R01

21" AMG Twin 5-Spoke

295/30 R21 on 10.5J x 21 ET42 (Front);
305/30 R21 on 11J x 21 ET33 (Rear)

**RWK - 21" AMG Forged Split 5-Spoke
Wheels, Black**

21"


B51; R01

21" AMG Twin 5-Spoke, Black

295/30 R21 on 10.5J x 21 ET42 (Front);
305/30 R21 on 11J x 21 ET33 (Rear)



LIMITED AVAILABILITY



**RWL - 21" AMG Forged Split Spoke,
Black**

21"

B51; R01

21" AMG Forged Split 5-Spoke

295/30 R21 on 10.5J x 21 ET42 (Front);
305/30 R21 on 11J x 21 ET33 (Rear)

**RWE - 21" AMG Forged Cross-Spoke,
Black**

21"

B51; R01

21" AMG Forged Cross-Spoke, Black

295/30 R21 on 10.5J x 21 ET42 (Front);
305/30 R21 on 11J x 21 ET33 (Rear)

**RWD - 21" AMG Forged Cross-Spoke,
Silver**

21"

B51; R01

21" AMG Forged Cross-Spoke, Silver

295/30 R21 on 10.5J x 21 ET42 (Front);
305/30 R21 on 11J x 21 ET33 (Rear)

**RWM - 21" AMG Forged Split Spoke,
Gold**

21"

B51; R01

21" AMG Forged Split 5-Spoke

295/30 R21 on 10.5J x 21 ET42 (Front);
305/30 R21 on 11J x 21 ET33 (Rear)

Code	Wheel Size	Description	Wheel Dimensions	Mobility	Availability	MSRP
RTM	20"	20" AMG Aero Twin 10-Spoke	295/30 R20 on 10.5J x 20 ET42 (front); 305/30 R20 on 11J x 20 ET33 (rear)	B51; R01	All Models	\$0
RVN	20"	20" AMG Multispoke	295/35 R20 on 10.5J x 20 ET42 (Front); 305/35 R20 on 11J x 20 ET33 (Rear)	B51; R01	All Models	\$0
RWI (Delayed)	21"	21" AMG Twin 5-Spoke	295/30 R21 on 10.5J x 21 ET42 (Front); 305/30 R21 on 11J x 21 ET33 (Rear)	B51; R01	All Models	
RWK (Delayed)	21"	21" AMG Twin 5-Spoke, Black	295/30 R21 on 10.5J x 21 ET42 (Front); 305/30 R21 on 11J x 21 ET33 (Rear)	B51; R01	All Models	
RWL	21"	21" AMG Forged Split 5-Spoke	295/30 R21 on 10.5J x 21 ET42 (Front); 305/30 R21 on 11J x 21 ET33 (Rear)	B51; R01	All Models	
RWE	21"	21" AMG Forged Cross-Spoke, Black	295/30 R21 on 10.5J x 21 ET42 (Front); 305/30 R21 on 11J x 21 ET33 (Rear)	B51; R01	All Models	
RWD	21"	21" AMG Forged Cross-Spoke, Silver	295/30 R21 on 10.5J x 21 ET42 (Front); 305/30 R21 on 11J x 21 ET33 (Rear)	B51; R01	All Models	
RWM (Limited Availability)	21"	21" AMG Forged Split 5-Spoke	295/30 R21 on 10.5J x 21 ET42 (Front); 305/30 R21 on 11J x 21 ET33 (Rear)	B51; R01	GT63R4	\$4,000

Upholstery

Nappa Leather



801 - Black Nappa Leather

Possible to upgrade headliner to Black Microfiber (61U)




804 - Sienna Brown / Black Nappa Leather

Possible to upgrade headliner to Black Microfiber (61U)

N/A w/ paint 993

AMG Performance Seats Shown



807 - Red Pepper / Black Nappa Leather

Possible to upgrade headliner to Black Microfiber (61U)

N/A w/ paint 970, 593, 964, 993



808 - Sage Grey / Black Nappa Leather

Possible to upgrade headliner to Black Microfiber (61U)

N/A w/ paint 970, 593



824 - MANUFAKTUR Tartufo Brown / Black Nappa Leather

Must select 61U (Black)

N/a w/ paint 993




825 - MANUFAKTUR Crystal White / Black Nappa Leather

Must select 61U (Black) Choice of U17 (Black) or Y03 (Grey) seatbelts.

AMG Performance Seats Shown

DELAYED



835 - MANUFAKTUR Macchiato Beige / Titanium Grey Nappa Leather

Requires 565 : Rear Seats. Must select one of 61U (Black) or 65U (Beige) Microfiber Headliner. Choice of U17 (Black) or Y02 (Beige) seatbelts.

N/a w/ paint 993



701 - Black Nappa Leather / Microfiber w/ Yellow Contrast Stitching

Requires AMG Performance Seats (555); omits standard Multicontour Seats. Omits standard Heated and Ventilated Front Seats (Only heated seats possible - 873). Choice of Yellow (Y06) or Black (U17) seatbelts. Must select Black Microfiber Headliner (61U)



711 - Black Nappa Leather / Microfiber w/ Red Contrast Stitching

Requires AMG Performance Seats (555); omits standard Multicontour Seats. Omits standard Heated and Ventilated Front Seats (Only heated seats possible - 873). Choice of Red(Y05) or Black (U17) seatbelts. Must select Black Microfiber Headliner (61U)

<i>Code</i>	<i>Description</i>	<i>Availability</i>	<i>Price</i>
801	Black Nappa Leather	All Models	\$0
804	Sienna Brown / Black Nappa Leather	All Models	\$0
807	Red Pepper / Black Nappa Leather	All Models	\$0
808	Sage Grey / Black Nappa Leather	All Models	\$0
824	MANUFAKTUR Tartufo Brown / Black Nappa Leather Must select 61U (Black)	All Models	
825	MANUFAKTUR Crystal White / Black Nappa Leather Must select 61U (Black) Choice of U17 (Black) or Y03 (Grey) seatbelts.	All Models	
835 (Delayed)	MANUFAKTUR Macchiato Beige / Titanium Grey Nappa Leather Requires 565 : Rear Seats. Must select one of 61U (Black) or 65U (Beige) Microfiber Headliner. Choice of U17 (Black) or Y02 (Beige) seatbelts.	All Models	
701	Black Nappa Leather / Microfiber w/ Yellow Contrast Stitching	All Models	
711	Black Nappa Leather / Microfiber w/ Red Contrast Stitching	All Models	

<i>Code</i>	<i>Upholstery</i>	<i>Seats</i>	<i>Floor Mats</i>	<i>Upper Dash/Lower Dash</i>	<i>Seat Belts</i>	<i>Steering Wheel</i>	<i>Headliner</i>
801	Black Nappa Leather	Black	Black	Black	Black	Black	Black Cloth
804	Sienna Brown / Black Nappa Leather	Sienna Brown	Black	Black / Sienna Brown	Black	Black	Black Cloth
807	Red Pepper / Black Nappa Leather	Red Pepper	Black	Black / Red Pepper	Black	Black	Black Cloth
808	Sage Grey / Black Nappa Leather	Sage Grey	Black	Black / Sage Grey	Black	Black	Black Cloth
824	MANUFAKTUR Tartufo Brown / Black Nappa Leather Must select 61U (Black)	Tartufo Brown	Black	Black / Tartufo Brown	Black	Black	Macchiato Beige or Black Microfiber
825	MANUFAKTUR Crystal White / Black Nappa Leather Must select 61U (Black) Choice of U17 (Black) or Y03 (Grey) seatbelts.	Macchiato Beige	Macchiato Beige	Black / Macchiato Beige	Macchiato Beige or Black	Macchiato Beige	Macchiato Beige or Black Microfiber
835 (Delayed)	MANUFAKTUR Macchiato Beige / Titanium Grey Nappa Leather Requires 565 : Rear Seats. Must select one of 61U (Black) or 65U (Beige) Microfiber Headliner. Choice of U17 (Black) or Y02 (Beige) seatbelts.	Macchiato Beige	Macchiato Beige	Black / Macchiato Beige	Macchiato Beige or Black	Macchiato Beige	Macchiato Beige or Black Microfiber
701	Black Nappa Leather / Microfiber w/ Yellow Contrast Stitching	Black w/ Yellow contrast stitching	Black	Black / Black	Yellow or Black	Black	Black Microfiber
711	Black Nappa Leather / Microfiber w/ Red Contrast Stitching	Black w/ Red contrast stitching	Black	Black / Black	Red or Black	Black	Black Microfiber

Trims



H80 - Black Piano Lacquer trim



H70 - AMG Aluminum Trim



H73 - AMG Carbon Fiber trim



H94 - AMG Dark Chrome Trim

<i>Code</i>	<i>Description</i>	<i>Availability</i>	<i>Price</i>
H80	Black Piano Lacquer trim	All Models	\$0
H70	AMG Aluminum Trim	All Models	
H73	AMG Carbon Fiber trim	All Models	
H94	AMG Dark Chrome Trim	All Models	

Packages

<i>Code</i>	<i>Packages</i>	<i>Availability</i>	<i>MSRP</i>
DA2	Driver Assistance Package <ul style="list-style-type: none"> ▪ Active Emergency Stop Assist ▪ Active Steering Assist ▪ Active Lane Keeping Assist ▪ Route-Based Speed Adaptation ▪ Active Lane Change Assist ▪ Evasive Steering Assist ▪ Active Brake Assist w/ Cross-Traffic Function ▪ Active Speed Limit Assist ▪ Active Blind Spot Assist ▪ Active Distance Assist DISTRONIC 	All Models	
DC1	AMG Night Package <ul style="list-style-type: none"> ▪ Darkened AMG-Specific Radiator Grille ▪ AMG Extended Night Package ▪ Model Badging in Black ▪ AMG Night Package 	All Models	
DC3 (Delayed)	Aerodynamics Package <ul style="list-style-type: none"> ▪ AMG Fixed Rear Spoiler in High Gloss Black ▪ Aerodynamamics Package 	All Models	
DC4	AMG Carbon Fiber Package Not with DC1 <ul style="list-style-type: none"> ▪ Exterior Mirror Housings in Carbon Fiber ▪ Carbon Fiber Exterior 	All Models	

Options

Factory Options

<i>Code</i>	<i>Options</i>	<i>Availability</i>	<i>MSRP</i>
399	Multicontour Front Seats w/ Massage Function Standard on GT63 , Requires (401) Heating and Ventilated Seats	GT55R4	
401	Heating and Ventilated Seats Standard on GT63	GT55R4	
416	Panoramic Sunroof	All Models	
438	Head-up Display Standard on GT63	GT55R4	
565 (Delayed)	Rear Seats with Folding Backrests	All Models	
479	Front Axle Lift	All Models	
77B	MBUX Interior Assistant	All Models	
750	AMG Exterior Chrome Package N/A on GT63	GT55R4	
811	Burmester High-End 3D Surround Sound System	All Models	
873	Heated Front Seats Required with 7xx level upholstery	All Models	\$0
874	MAGIC VISION CONTROL Windshield Wipers	All Models	
942	Load Compartment Package	All Models	\$485
C52	Indoor Car Cover	All Models	
L6J	AMG Performance Steering Wheel in Nappa Leather	All Models	\$0
L6K	AMG Performance Steering Wheel in Nappa / Microfiber	All Models	
L6H	AMG Performance Steering Wheel in Microfiber / Carbon Fiber Design	All Models	
P53	Energizing Air Control	All Models	
P82	Guard 360	All Models	
PBR	ENERGIZING Package Plus N/A with 701/711	All Models	
U17	Omission of Color Seatbelts	All Models	\$0
U19	MBUX Augmented Reality for Navigation Standard on GT63	GT55R4	\$0
Y02	Macchiato Beige Seatbelts Only w/ 835	All Models	\$0
Y03	Neva Grey Seatbelts Only w/ 825	All Models	
Y05	Red Seatbelts Only w/ 711	All Models	
Y06	Yellow Seatbelts Only w/ 701	All Models	
51U	Black Cloth Headliner	All Models	\$0
61U	Black Microfiber Headliner	All Models	
65U	Macchiato Beige Microfiber Headliner Only w/ 824 or 835	All Models	
B07 (Limited Availability)	AMG Carbon Ceramic Brakes	All Models	
21U	Dash Cam	All Models	\$200
6U6 (New)	AMG Fuel Cap		
555	AMG Performance Seats Omits standard Multicontour Seats w/ Massage	All Models	
409	Additional adjustability for AMG Performance Seats Requires AMG Performance Seats (555); Omits standard Multicontour Seats w/ Massage	All Models	

VPC Installed Options

<i>Code</i>	<i>Options</i>	<i>Availability</i>	<i>MSRP</i>
D07	Wheel Locking Bolts		\$160
D43	All-Season Floor Mats - 4 Pack		\$170
D49	First Aid Kit		\$35
D38	AMG Star Set (plate frame/valve caps/keychain)		\$85

Specifications

GT55R4



Chassis

Chassis and Body Construction

Aluminum space frame; intelligent material mix of aluminum, steel, magnesium and fiber composites throughout the vehicle

Vehicle Type

Two-door Coupe

Suspension

Front Suspension

AMG ACTIVE RIDE CONTROL suspension with semi-active anti-roll stabilization, aluminum double wishbones, anti-dive control, coil springs and adaptive adjustable damping

Rear Suspension

AMG ACTIVE RIDE CONTROL suspension with semi-active anti-roll stabilization, aluminum double wishbones, anti-dive control, coil springs and adaptive adjustable damping

Drivetrain

Transmission

AMG SPEEDSHIFT MCT 9G (9 speed)

Drive Configuration

AMG Performance 4MATIC+ all-wheel drive with variable torque distribution

Wheels and Tires

Standard Wheel Size

Front: 10.5" x 20" / Rear: 11" x 20"

Standard Tire Size

Front: 295/30 R 20 / Rear: 305/30 R 20

Standard Wheel Offset (mm)

Front: ET 42 / Rear: ET 33

Brakes

Front Brakes

15.4" composite brake discs, vented and perforated; 6-piston aluminum fixed caliper

Rear Brakes

14.2" composite brake discs, vented and perforated; 1-piston aluminum floating caliper

Engine

Engine Configuration

Handcrafted AMG 4.0L V8 biturbo

Displacement (cc)

3,982

Bore (in / mm)

3.27 / 83.0

Stroke (in / mm)

3.62 / 92.0

Compression Ratio

8.6 : 1

Power (hp)

469 hp @ 5,500 - 6,500

Torque (lb-ft)

516 lb-ft @ 2,500 - 5,000

Fuel Requirement (Octane)

91

Fuel Tank Size (gallons)

18.5

Redline (rpm)

7,000

Performance

Acceleration 0-60 mph (sec)

3.8 (est)

Top Speed (mph)

183 (est)

Fuel Economy

City Fuel Economy (mpg)

TBA

Highway Fuel Economy (mpg)

TBA

Combined Fuel Economy (mpg)

TBA

Gas Guzzler Tax

TBA

Exterior Dimensions

Vehicle Length (in.)

186

Vehicle Height (in.)

53.3

Vehicle Width w/o exterior mirrors (in.)

79.3

Wheelbase (in.)

106.3

Curb Weight (lbs)

77.6

Track Width Front/Rear (in.)

66.3 / 66.4

Interior Dimensions

Cargo Capacity

11.3 cu. ft. : w/ Rear Seats folded down - 23.8 cu. ft.

Chassis

Chassis and Body Construction Aluminum space frame; intelligent material mix of aluminum, steel, magnesium and fiber composites throughout the vehicle

Vehicle Type Two-door Coupe

Suspension

Front Suspension AMG ACTIVE RIDE CONTROL suspension with semi-active anti-roll stabilization, aluminum double wishbones, anti-dive control, coil springs and adaptive adjustable damping

Rear Suspension AMG ACTIVE RIDE CONTROL suspension with semi-active anti-roll stabilization, aluminum double wishbones, anti-dive control, coil springs and adaptive adjustable damping

Drivetrain

Transmission AMG SPEEDSHIFT MCT 9G (9 speed)

Drive Configuration AMG Performance 4MATIC+ all-wheel drive with variable torque distribution

Wheels and Tires

Standard Wheel Size Front: 10.5" x 20" / Rear: 11" x 20"

Standard Tire Size Front: 295/30 R 20 / Rear: 305/30 R 20

Standard Wheel Offset (mm) Front: ET 42 / Rear: ET 33

Brakes

Front Brakes 15.4" composite brake discs, vented and perforated; 6-piston aluminum fixed caliper

Rear Brakes 14.2" composite brake discs, vented and perforated; 1-piston aluminum floating caliper

Engine

Engine Configuration Handcrafted AMG 4.0L V8 biturbo

Displacement (cc) 3,982

Bore (in / mm) 3.27 / 83.0

Stroke (in / mm) 3.62 / 92.0

Compression Ratio 8.6 : 1

Power (hp) 577 hp @ 5,500 - 6,500

Torque (lb-ft) 590 lb-ft @ 5,500 - 6,500

Fuel Requirement (Octane) 91

Fuel Tank Size (gallons) 18.5

Redline (rpm) 7,000

Performance

Acceleration 0-60 mph (sec) 3.1 (est)

Top Speed (mph) 196 (est)

Fuel Economy

City Fuel Economy (mpg) TBA

Highway Fuel Economy (mpg) TBA

Combined Fuel Economy (mpg) TBA

Gas Guzzler Tax TBA

Exterior Dimensions

Vehicle Length (in.) 186

Vehicle Height (in.) 53.3

Vehicle Width w/o exterior mirrors (in.) 79.3

Wheelbase (in.) 106.2

Curb Weight (lbs) 77.6

Track Width Front/Rear (in.) 66.3 / 66.4

Interior Dimensions

Cargo Capacity 11.3 cu. ft. : w/ Rear Seats folded down - 23.8 cu. ft.

Options In Detail

Completely new bodyshell



The sophisticated bodyshell of the new AMG GT is the basis for high performance and driving comfort. A sibling frame to that of the new SL (R 232), it also relies on an intelligent material mix of an aluminum spaceframe architecture together with high-strength steels and magnesium. One example of intelligent use of materials is the greenhouse of the new GT, where it is structurally designed with lightweight and high-strength steel to meet the high safety requirements at Mercedes-Benz, without sacrificing performance.

Due to the high stability of steel, less material can be used resulting in a lower weight. In addition, further local stiffening measures come into play, for example the GT's closed coupé frame was adapted to further increase torsional stiffness (+ approx. 40 % compared with the SL) to prevent twisting of the frame when driving.

Handcrafted AMG 4.0L V8 Biturbo Engine



For use in the GT, the internally named M 177 engine received a new oil pan, repositioned intercoolers and active crankcase ventilation. The intake and exhaust ducts have been optimized for even more effective gas exchange and the exhaust gas routing for the catalytic converter box and petrol particulate filter has been enlarged. The developers achieved the increased output of the GT 63 primarily through higher boost pressure and greater air flow, as well as modified engine software. To sum up, the eight-cylinder engine thrills with its exceptional power delivery and powerful acceleration in all engine speed ranges combined with maximum efficiency for low consumption and emission values.

In the GT 55, the engine produces 469 hp and provides a maximum 516 lb-ft of torque over a range of 5,500 to 6,500 rpm. At a standstill the vehicle is able to reach 60 mph in an estimated 3.8 seconds.

The engine in the GT 63 develops 577 hp and provides a maximum torque of 590 lb-ft over a wide rev range from 5,500 to 6,500 rpm. The 2-door coupé's top engine thus conveys effortless superiority in every rev range. The acceleration from 0 to 60 mph in an estimated 3.1 seconds illustrates this.

AMG SPEEDSHIFT MCT 9G transmission



The AMG SPEEDSHIFT MCT 9G transmission (MCT = Multi-Clutch Transmission) is specially adapted to the requirements of the new GT. A wet start-off clutch replaces the torque converter. It reduces weight and, thanks to its lower inertia, optimizes response to accelerator pedal commands, especially during spurts and load changes. The elaborately calibrated software ensures extremely short shift times and, if required, fast multiple downshifts and, thanks to the throttle blip function in the "Sport" and "Sport+" driving modes, delivers a particularly emotionally appealing gearshift experience. Here, defined ignition adjustments enable even faster gearshifts than in the other modes. In all modes moving off occurs in first gear in order to always guarantee a dynamic driving experience. There is also the RACE START function which ensures optimal acceleration from a standstill.

The highlights of the transmission include:

- Adaptation of the shift characteristics to the selected AMG DYNAMIC SELECT driving mode
- In manual mode "M," the transmission responds immediately and precisely to manual gearshift commands from the driver and implements the commands at lightning speed
- Automatic throttle blipping function when downshifting: This effect is automatically active in the "Sport", "Sport+" and "RACE" driving modes (standard on the GT 63)
- ECO start/stop function is automatically active in the "Comfort" driving mode
- The "gliding" mode can be activated in the "Individual" driving mode

AMG Performance 4MATIC+



For the first time the GT 2-door is available with a drive system acting on all four wheels. The model is equipped with AMG Performance 4MATIC+ fully variable all-wheel drive as standard. This intelligent system combines the advantages of different drive concepts: the fully variable torque distribution to the front and rear axles ensures optimal traction right up to the physical limit. The driver is also able to rely on high handling stability and a high level of safety under all conditions: in the dry, in the wet or in snow. The transition from rear-wheel to all-wheel drive and vice versa takes place continuously on the basis of a sophisticated matrix that integrates the intelligent control into the entire vehicle systems architecture.

An electromechanically controlled clutch connects the permanently driven rear axle variably to the front axle. The best possible torque split is continuously computed according to the driving conditions and driver's input. This means that the new roadster can be driven continuously variably from traction-oriented all-wheel drive to pure rear-wheel drive. Alongside traction and lateral dynamics, the all-wheel drive also improves the longitudinal dynamics for even more powerful acceleration.

AMG DYNAMIC PLUS Package




Standard on the GT 55 and GT 63

The AMG DYNAMIC PLUS Package, designed for the ultimate driving enjoyment and supreme agility. It combines numerous high-performance components in an attractive package for further improved driving dynamics.

From visible distinction in the form of yellow-painted AMG brake calipers to experiential with the unique RACE drive program featuring drift mode. Additional components include an electronically controlled AMG limited-slip differential on the rear axle, dynamic engine mounts, and a 10mm lowered suspension, all set with the purpose to provide the most thrilling driving experience.


- AMG brake callipers painted in yellow (U69)
- "RACE" drive program including Drift mode
- AMG dynamic engine mounts (466)
- AMG rear axle locking differential, electronic (467)
- Suspension lowered by 10 mm

Rear-axle Steering



For the first time, the GT is equipped with 2.5 degree active rear-axle steering as standard. Depending on the speed, the rear wheels steer either in the opposite direction (up to 62 mph, or 100 km/h) or in the same direction (faster than 62 mph, or 100 km/h) as the front wheels. The system thus enables both agile and stable handling - characteristics that are in contrast to each other without rear-axle steering. Other advantages include easier vehicle control at the limits and less steering effort because the front-wheel steering ratio is more direct.

Standard Active Aerodynamic Elements




A technical highlight in the aero development: the active air control system AIRPANEL. AIRPANEL features vertical louvers hidden behind the lower air intake in the front bumper. Normally the louvers are closed, this position reduces drag and allows the air to be directed specifically towards the underbody and also reduces front lift. Only when certain temperatures on predefined components are reached and the demand for cooling air is particularly high do the louvers open and allow maximum cooling air to flow to the heat exchangers.

Another active component is the retractable rear spoiler seamlessly integrated into the trunk lid. It changes its position depending on the driving status. In doing so, the control software takes into account numerous parameters: it factors the driving speed, the longitudinal and lateral acceleration and the steering speed into the calculation. The spoiler assumes five different angular positions from 50 mph (80 km/h) to either optimize handling stability or reduce drag.

Exclusively Standard on the GT is also an active aerodynamic element which is hidden in the underbody in front of the engine, and also contributes to the improved handling. This carbon profile, which weighs around 12 pounds (5.5 kilograms), reacts to the setting of the AMG driving modes and automatically extends downwards by around 1.6 inches (40 mm) at a speed of 50 mph (80 km/h). This creates a Venturi effect, which sucks the car to the road surface and reduces front-axle lift. The driver feels this positively in the steering: the GT can be steered even more precisely into bends and tracks even more stably.

AMG Aerodynamics Package (DC3)




Get the most out of your vehicle with the AMG Aerodynamics Package, you can specifically sharpen the looks while benefiting from improved driving characteristics. This package consists of a function fixed rear wing that generates additional downforce on the rear axle (+31 lbs at 155mph / 48.5 lbs at 195mph) for better performance.

Currently Delayed Feature - When equipped with Carbon Fiber Exterior Package, Fixed Rear Spoiler will be in Carbon Fiber

- Front apron with flics on the air intakes and wheel arches in high-gloss black
- Rear apron with flics on the side air outlets in high-gloss black
- Diffuser attachment at the rear in high-gloss black

AMG Carbon Fiber Package (DC4)



The AMG Carbon Fiber package allows the customer to make the GT even more dynamic. The package includes the following parts in carbon: **front splitter**, **inserts in the side sills**, the **exterior mirror housings**, **diffuser** as well, **inserts in the blade of the static rear wing** (in conjunction with AMG Aerodynamics package). In addition, the tailpipe trims are black chrome-plated and the roof edge trim bar and the trim element of the wings are in high-gloss black.

P82 GUARD 360

GUARD 360 vehicle protection provides all-round monitoring. It comprises an anti-theft alarm system plus tow-away protection that is able to detect changes in position. Movement in the vehicle interior also triggers visual and acoustic warnings. After-theft help also increases the chances of you recovering your property.

- Parking damage detection
- Theft/towing notification
- Camera Snapshots in headunit and app icw w. 360° Surroundview Camera

Gallery

All

Exterior

Interior

