


- 1 Water drain hose
- 2 Bolts (self-tapping)
- 3 Bolt (metric thread)
- 4 Seal
- 6 Tilting/sliding roof frame




P77.20-2387-06

7.12.06

Shown on model 211.0

- 2 Bolts (self-tapping)
- 5 S Asembly plier



P77.20-2271-04

Modification notes


1.3.06 Repair method completely modified Steps 1.	1 to 12
---	---------

XX	Remove/install		
1.1	Remove paneling from tilting/sliding roof	When replacing tilting/sliding roof frame (6).	AR77.20-P-0500T
2.1	Remove tilting/sliding roof panel	When replacing tilting/sliding roof frame (6).	AR77.20-P-1000T
3.1	Loosen headliner and lay down on seat backrests with electrical lines connected.	Model 211.0	AR68.30-P-4300TA
		Model 211.2	AR68.30-P-4300TD
4.1	Remove front headliner	Model 240.0	AR68.30-P-7607HA
5.1	Remove rear headliner	Model 240.0	AR68.30-P-7608H
6.1	Disconnect all electrical connectors from roof crossbeam, expose wiring harnesses, disconnect cable tie and remove roof crossbeam.	Model 240.0	
7	Remove water drain hoses (1)	Do not damage water drain hoses (1), otherwise damage can be caused by penetrating water.	
8	Insert assembly pliers (5) on both sides	<u>S</u>	*202589013700
9	Unscrew bolts (2, 3)	i Installation: Do not mix up screws (2, 3).	*BA77.20-P-1003-01A
10	Remove tilting/sliding roof frame (6) from vehicle.	 Simultaneously remove both assembly pliers (5), otherwise tilting/sliding roof frame (6) can be damaged. Aid of helper required. 	

		i Installation: Replace seal (4).	
11	Install in the reverse order		
12	Perform teach-in run for sliding roof anti-pinch protection		
₩ A D	Connect STAR DIAGNOSIS and read out fault memory		AD00.00-P-2000-04A

Mm Electric sliding roof

Number	Designation	Model 211	Model 240
BA77.20-P-1003-01A	Bolt to tilting/sliding roof frame Nn	8	8



@ Daimler AG, 8/22/17, B/08/17/X, ar77.20-p-3000t, Remove/install tilting/sliding roof frame MODEL 211.0 /2, 240.0 with CODE (414) Power glass tilting/sliding roof