
AR82.30-P-6400CW Remove/install wiper system MODEL 204, 207, 212, 218


Shown on model 204.0/2

- 1 Driver-side wiper arm
- Passenger-side wiper arm 2
- 3 Frame seal center piece
- 4 Screw
- 5 6 Strut
- Water collector



P82.30-2632-11

27.9.11



P82.30-2665-07

Shown on model 204.0/2


- 7 Nut
- 8 Wiper system


Model 218

R2/10x1 Wiper park position heater electrical connector

Screw

9 10 Electrical connector 11 Bracket





P82.30-2969-04

Modification notes

10.8.10	Value changed: Nut for strut to suspension strut tower	*BA62.30-P-1006-02G

XX	Remove/install		
	Risk of injury caused by moving parts that can pinch, crush or, in extreme cases even sever extremities.		AS82.30-Z-0001-01A
1	Remove driver-side wiper arm (1) and passenger-side wiper arm (2)		AR82.30-P-6100CW
2	Remove frame seal center piece (3)	In model 204, 207, 212	
3	Remove water collector (6)		
4	Remove strut (5)	■ On model 204 the strut (5) is attached with the bolt (4) of the suspension strut.	*BA32.25-P-1003-04M

		On model 207 the strut (5) is fastened below the windshield using the bolt (4) of the suspension strut and two nuts. Mm Mm In model 212 and 218 the strut (5) is attached to the mounting console with a nut. Mm	*BA32.25-P-1003-04M *BA62.30-P-1007-02G *BA62.30-P-1006-02G
5	Unscrew bolt (9)	Do not change installation position of bracket (11) at partition wall, since this would change the contact pressure of the wiper arms and therefore the wiping area.	*BA82.30-P-1002-01M
6	Unscrew nuts (7)	Nm	*BA82.30-P-1003-01M
7	Disconnect electrical connector (10) on wiper motor		
8	Unplug wiper park position heater electrical connector (R2/10x1)	Model 218 Unplug wiper park position heater electrical connector (R2/10x1) carefully to avoid damaging the wiper park position heater connections. Unlock wiper park position heater electrical connector (R2/10x1) at the catch tab (arrow A), detach from holder and unplug. Unclip wiring harness bracket (arrows B) from wiper system.	
9	Remove wiper system (8)		
10	Install in the reverse order	i Installation: Before installing a new wiper system (8), the bracket (11) of the new wiper system (8) must be removed.	

Nm Suspension struts

Number	Designation	Model 204.00/02/04/05/ 06/20/22/24/25/ 30/33/34/35 without code 483	Model 204.00/02/04/05/ 06/20/22/24/25/ 30/33/34/35 with code 483, model 204.077/277/ 377
BA32.25-P-1003-04M	Suspension strut to body Nm	33	33

Nm Suspension struts

Number Designation BA32.25-P-1003-04M Suspension strut to body		Model 204.08/09/28/29/ 38/9
BA32.25-P-1003-04M	Suspension strut to body Nm	33

Nm Suspension struts

Number	Designation	Model 207 without code 483	Model 207 with code 483
--------	-------------	----------------------------------	-------------------------------

BA32.25-P-1003-04M	Suspension strut to body	Nm	33	33

M Front end assembly with front reinforcement

Number	Designation	Model 212	Model 218
BA62.30-P-1006-02G	Nut, strut to suspension strut tower Nm	30	30

$\fbox{\sc Mm}$ Front end assembly with front reinforcement

Number	Designation	Model 207.3	Model 207.4
BA62.30-P-1007-02G	Nut, strut to firewall Nm	35	35

^{Nm} Windshield wiper

Number	Designation	Model 204	Model 207	Model 212	Model 218
BA82.30-P-1002-01M	Bolt, wiper system to bracket Nm	11	11	11	11
BA82.30-P-1003-01M	Nut, wiper system to body Nm	20	22	22	22