
Model 218



P68.10-4346-09

Glove compartment 2

Passenger side trim pieces

Bolts

Instrument panel

5 Air duct

X29/1 Glove compartment electrical connector

With CODE 508 (Navigation box preinstallation) or with CODE 509 (Navigation box)

Glove compartment A2/30-1 Cradle for navigation module



P68.10-4776-01

(1)	Information on preventing damage to electronic components due to electrostatic discharge	AH54.00-P-0001-01A
XX	Remove/install	
1	Remove right cover below dashboard (4)	
2	Remove passenger side trim pieces (2) from instrument panel (4)	AR68.10-P-1180EL
3	Remove bolts (3)	

4	Remove glove compartment (1) from instrument panel (4) until electrical connectors on glove compartment (X29/1) are accessible	i Model 218 with code 508 (Navigation box preinstallation) Model 218 with code 509 (Navigation box) Observe electrical connectors on holder for navigation module (A2/30-1).	
5	Disconnect electrical connector for glove compartment (X29/1)		
6	Disconnect electrical connectors from holder for navigation module (A2/30-1)	Model 218 with code 508 (Navigation box preinstallation) Model 218 with code 509 (Navigation box)	
7	Remove glove compartment (1)		
8	Remove holder for navigation module (A2/30-1) from glove compartment (1)	Model 218 with code 508 (Navigation box preinstallation) Model 218 with code 509 (Navigation box) When replacing glove compartment (1)	
9	Install in the reverse order	i Installation: Ensure that connection (arrow) of air duct (5) on glove compartment (1) is seated correctly.	